

FIGURE 400-A: SPHERICAL SLIP-IN WELDED JOINT (SSJ)

SPHERICAL SLIP IN JOINTS ARE THE DEFAULT JOINT FOR MAINS \leq DN900.

FIGURE 400-B: BALL AND SOCKET JOINT (B&S)

BALL AND SOCKET JOINTS ARE THE DEFAULT JOINT FOR MAINS $>$ DN900 AND PROVIDE A GREATER DEGREE OF JOINT FLEXIBILITY AT THESE SIZES.




FIGURE 400-C: PLAIN END WELDED COLLAR JOINT (WC)

FIGURE 400-D: PLAIN ENLD WELDED COLLAR JOINT (WC) FOR MAINS \geq DN750




FIGURE 400-D: STEEL MAIN INSULATED TAPPING ARRANGEMENT

NOTES Regarding Insulated Tappings:

- Tapping of steel mains is generally not acceptable for mains \geq DN375 and requires water agency approval.
- Steel tapping pad shall be pre tapped and fillet welded onto the pipe around the entire perimeter.
- All exposed steel shall be covered by protective tape to 150mm over native pipe coating as described in drawing MRWA-W-306A.
- Only protective tape and mastic system shall be used (not PE shrink wrap).
- Stretch tape tightly around barrel union, mastic and tapping pad to prevent water / air ingress.
- Tape shall be wound continuously over clean and primed pipe.

NOTES on Corrosion Protection:

- Corrosion protection described here is required for all steel surfaces which do not have a high integrity coating consisting of one of the following:
 - Heat applied MDPE coating to AS4321.
 - Fusion bonded epoxy coating to AS/NZS 4158.
- Bare, bitumen coated or painted surfaces are not acceptable coatings. These surfaces will be referred to as uncoated.
- All corrosion protection products shall be as per the water agency product catalogue. The manufacturers instructions must be available for reference on site.
- Products from a single manufacturer shall be used to ensure compatibility of products. All products shall be applied as per the manufacturers instructions.
- Step 1: Surface Preparation- All surfaces to be primed shall be prepared to a finish of class SA2.5 according to AS1627.2. Power wire brush remove all scale, loose rust and old flanking coating. Chisel off all weld splutter and slag.
- Step 2: Primer- Shall be applied by brush or spray to all uncoated surfaces to a distance of 200mm over the pipe native coating. The entire area to be wrapped shall be primed, including all flanges and bolts.
- Step 3: Mastic- Mastic is only required where projections greater than 3mm occur (therefor fillet welds will only need to be mastic contoured when the plate thickness is $>$ 3mm thicker than the fillet weld). Mastic will be required around all tappings. Apply mastic to create a gradual and smooth transition from the pipe to the outer surface. Apply mastic by hand, ensuring no significant voids are present.
- Step 4- Option A: MDPE shrink wrap- MDPE shrink wrap shall be undertaken in accordance with clause "reinstatement using heat shrinkable wrapping system" clause in Part 2 of WSA03, MRWA edition. Only suitable for flat surfaces (ie: SSJ, B&S or WC joints).
- Step 6: DCVG Holiday Testing- Where requested or specified by the water agency, DCVG holiday detection testing shall be undertaken to confirm the integrity of the pipeline coating system in accordance with AS4827.1- coating defect surveys for buried pipelines- direct current voltage gradient (DCVG).

GENERAL NOTES:

- For steel pipelines, only SSJ, B&S, WC and flanged joints are acceptable. RRJ mains require water agency approval.
- Pipes to be joined in accordance with manufacturers handling and installation manual.
- Gaps in the internal cement mortar lining shall be reinstated and internal seams welded for all mains \geq DN750.
- Welding and the non destructively testing of welds shall be undertaken in accordance with clause "welding of steel pipelines" clause in Part 2 of WSA03, MRWA edition.
- Fitting shall be fabricated in accordance with clause "fabrication of steel fittings" clause in Part 2 of WSA03, MRWA edition.
- For steel flange arrangements, refer to MRWA-W-306A & 306B.
- For Cathodic Protection requirements of steel mains, refer to the Water Agency's Cathodic Protection Standards (CORR specifications).
- Ensure test points are installed on cathodic protected mains as per the Cathodic Protection design and that mains on both sides of valves are protected (via bonding across a valve, separate anodes or separate ICCP units etc).

DESIGNED: R. JAGGER				DATE: 20/01/2011			
DRAWN: R. JAGGER				DATE: 20/01/2011			
3	REFORMATTING & REF CP DRAWINGS	1/06/16	RJ / CP / JT	CHECKED	NAME	DATE	APPROVED
2	PUBLISHED FIRST ISSUE	04/04/12	R. JAGGER	<input checked="" type="checkbox"/> GWW	C. RIVETTE	04/04/12	<input checked="" type="checkbox"/> GWW
1	PRE PUBLISHED DRAFT FOR COMMENT	12/07/11	R. JAGGER	<input checked="" type="checkbox"/> SEWL	C.PAXMAN	04/04/12	<input checked="" type="checkbox"/> SEWL
	REV	DESCRIPTION	DATE	APPROVED	<input checked="" type="checkbox"/> YVW	K.DAWSON	04/04/12
					<input checked="" type="checkbox"/> YVW	A.COSHAM	04/04/12

MELBOURNE RETAIL WATER AGENCIES

MRWA WATER SUPPLY STANDARD DRAWINGS

STEEL PIPELINE JOINTING

NOT TO SCALE

MRWA-W-400

ISSUED 2012 VERSION 3